SC2040M200F ALL-IN-ONE RING T-OH/UG 200A SEMI-FLUSH

Price*: 1671.00 USD

Main

Commercialised
All-In-One
Homeline
200 A
Ringed
OH with field installed tunnel kit UG
No bypass

Complementary

Short-circuit current	22 kA	
Product mounting	Semi-flush	
Number of spaces	20	
Number of circuits	40	
Number of tandem circuit breakers	20	
Hub type	A-L	
Electrical connection	Lugs service ground Lugs line side	
AWG gauge	4250 AWG/kcmil copper line side 4250 AWG/kcmil aluminium line side 122/0 AWG copper service ground 122/0 AWG aluminium service ground	
Device composition	Service disconnect (factory installed)	
Service disconnect rated current	200 A	
Branch circuit breaker rated current	200 A	

Ordering and shipping details

Category	00148 - HOMELINE CSED DEVICES	
Discount Schedule	DE3A	
GTIN	00785901107811	
Nbr. of units in pkg.	1	
Package weight(Lbs)	51.50	
Returnability	Y	
Country of origin	MX	

