



70.0 ± 2.8 @ 1.5 DIA.

ITEM NO	NAME	DESCRIPTION	MATERIAL	PCS/ASSM	COMPONENT NO	FT-PCS/100 ASSM	MAT'L COST/UNIT	LABOR COST/UNIT	MAT'L COST/100 ASSM	LABOR COST/100 ASSM
1	MESH	STRAND	GAU. STL.	—	373-01-010	1				
2	STRAND TAB, Q.W.	TUBE - FLATTENED	CU	6	312-43-028	3				
3	STRAND TAB, T.W.	TUBE - FLATTENED	CU	6	312-43-023	3				
4	END TAB	TUBE - FLATTENED	CU	6	312-43-021	3				
5	INSTRUCTIONS	INSTALLATION	PAPER	1	309-20-103					
6	FASTENER	TIE WRAP	PLASTIC	2	316-20-001					
7	TAG	IDENTIFICATION	MYLAR	1						



kellems division

HARVEY HUBBELL INC.  
Route 1, Lord's Hill  
Stonington, Conn.

TITLE GRIP, GAU. STL. - PULLING, REGULAR  
WIRE ROPE - CLOSED MESH, MULTI-  
WEAVE, DOUBLE ENDED  
FOR 1/8" OR 1/2" WIRE ROPE  
DESCR 1/8" & 1/2" RWR  
APPROX. QTY/STR 20,000 WT/100 (LBS)

MFG METHOD	SCALE	ASSEMBLY
STD	NONE	→
	SHEET (OF 1)	TOTAL
DRAWN BY	CHECKED BY	CALCULATED BY
R.S. 12/28/79		
TOLERANCES UNLESS OTHERWISE SPECIFIED		
.X ± .5	.XX ± .05	.XXX ± .015
ANGLE'S ± 2°		